


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 17 Twp. 21 Rge. 13 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 990' N. & 330' E. of S $\frac{1}{4}$  Cor.  
Lease Owner Cities Service Oil Company  
Lease Name Vink Well No. 2  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 14 19.51  
Application for plugging filed February 14 19.51  
Application for plugging approved February 14 19.51  
Plugging commenced February 14 19.51  
Plugging completed February 14 19.51  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ----- 19.-----

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3720 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	355'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 300 feet to 205 feet for each plug set.

3720' to 300' mud  
300' to 205' wood plug and 15 sacks cement  
205' to 35' mud  
35' to base of cellar, 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 6 1951  
CONSERVATION DIVISION  
Wichita, Kansas  
3-7-51

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to R. C. Cooper  
Address Box 751  
Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. M. Conover (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. M. Conover*  
Box 751, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of February, 19.51  
*W. G. Smith*  
Notary Public.

My commission expires March 12, 1951. 22-7877-8 4-49-10M

PLUGGING  
FILE SEC 17 T 21 R 13W  
BOOK PAGE 68 LINE 11

# WELL RECORD

15.185.11478.0000

Company Cities Service Oil Co. Well No. 2 Farm        Vint         
 Location 990' North and 330' East of S/4 Corner Sec. 17 T. 21 R. 13W  
 Elevation 1903 (1900 Cr.) County Stafford State Kansas  
 Drlg. Comm. February 4, 1951 Contractor Hola Drilling Company  
 Drlg. Comp. February 13, 1951 Acid None  
 T. D. 3720' Initial Prod. Dry Hole - P. & A. 2-11-51

CASING RECORD:

2-5/8" O 355' con. 250 wt cement

FORMATION RECORD:

surface soil	0-8
sand & clay	65
sand & iron	125
shale, shells & red bed	365
red bed	795
lime	815
shale & shells	1740
lime & shale	2420
shale & lime	2605
lime & shale	3175
lime	3250
shale	3370
lime	3430
lime & chert	3665
lime & shale	3578
shale & conglomerate	3597
shale	3713
limo	3720 T. D.

Top Lansing	3357'
Top Conglomerate	3616'
Top Viola	3619'
Top Simpson Shale	3656'
Top Simpson Sand	3674'
Top Artuckle	3713'
Penetration	7'
Total Depth	3720'

Drill stem test 3715-25, recovered  
 170' water in 30 mins.; 10 min.  
 B. H. P. 6907.

BYFO:	500'	1°
	1000'	1°
	1500'	1°
	2000'	0°
	2500'	1°
	3000'	0°

PLUGGING

FILE SEC 17 T 21 R 13W  
 BOOK PAGE 68 LINE 11

RECEIVED

STATE CORPORATION COMMISSION

MAR - 7 1951

CONSERVATION DIVISION  
 Wichita, Kansas