

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15.185.19558.0000

API NUMBER _____
 LEASE NAME Harms "F"
 WELL NUMBER #2
 SPOT LOCATION SW NE NW
 SEC. 17 TWP 21 RGE 13 (E) or (W) (W)
 COUNTY Stafford
 Date Well Completed 10-20-62
 Plugging Commenced 3-6-85
 Plugging Completed 3-21-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Petroleum Inc.
 ADDRESS Box 698, Great Bend, Ks. 67530
 PHONE #793-8968 OPERATORS LICENSE NO. 5238

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	240'	None
				5-1/2"	3657'	883.96'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 3300' and 5 sacks cement Shot casing at 2800' and 2600' casing parted. Pulled 28 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 4% added gel and 3% calcium chloride. Maximum pressure was 300 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
 Address Box 698, Great Bend, Kansas 67530

RECEIVED

STATE OF Kansas COUNTY OF Barton, ss.

APR - 1 1985

James W. Rockhold (employee of operator) or
 (operator) of above-described well, being first duly sworn on oath, says: That
 I have knowledge of the facts, statements, and matters herein contained and
 the log of the above-described well as filed that the same are true and
 correct, so help me God.

(Signature) James W. Rockhold
 (Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of March, 1985

NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-87

Iona M. Leatherman
 Notary Public

My Commission expires: