

44
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Kane Well No. # 1

Location C SE NW Sec. 17 Twp. 30 Rge. 17 (E) (W) W

County Kiowa Total Depth 4978

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:30AM Day 27th Month Sept. Year 1963

The Above well was plugged as follows:

215' of 10 3/4" surface pipe, cemented with 150 sacks. 4975' of 4 1/2"
long string, cemented with 150 sacks. Plugged back to 4918', Top perfor-
ation 4886'. Bottom of hole was sanded to 4870', and cemented with 3
sacks. Fluid level was up in hole. Plug was pushed to 220', 10' rock
bridge, and cemented through dump bailer with 1 sack Cal-Seal and 1 sack
cement and let set over night, Next morning hole bailed down and 30 sacks
cement was added to plug. Hole was filled with mud to 35', 10' rock bridge,
cemented with 10 sacks to base cellar. 3900' of 4 1/2" long string was recov-
ered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/30/63
INV. NO. 4805-W