


 KANSAS  
 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
 STATE CORPORATION COMMISSION

DEC 5 1966

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assitant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Operator's Full Name K & E Drilling, Inc.  
 Complete Address: 719 Union Center Bldg., Wichita, Kansas  
 Lease Name Kane-Barstow Well No. # 1  
 Location C NE NE Sec. 5 Twp. 30 Rge. 17 (E) (W) W  
 County Kiowa Total Depth 4915'  
 Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X       
 Other well as hereafter indicated:       
 Plugging Contractor: K & E Drilling, Inc.  
 Address: 719 Union Center Bldg., Wichita, Kansas License No.       
 Operation Completed: Hour 1:30PM Day 3rd Month Dec. Year 1966

The Above well was plugged as follows:

413' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole  
was filled with drilling mud to 400', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 400', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
 Well Plugging Supervisor

DATE 12/6/66

INV. NO. 4385-W