

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address: Box 48, Great Bend, Kansas

Lease Name Mellies "B" Well No. # 2

Location SE SW SE Sec. 36 Twp. 21 Rge. 12 (E) (W)W

County Stafford Total Depth 3574'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:15AM Day 21st Month Feb. Year 1966

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated. 3568' of 5 1/2" long String,
cemented with 100 sacks. Bottom of the hole was sanded to 3550', and cement-
ed with 5 sacks, through the dump bailer. 2848' of 5 1/2" long string was re-
covered from the hole. Fluid was up in the hole. Bridge plug was pushed in
fluid to 240', rock bridge from 240' to 230'. 5 sacks of cement was mixed in
a barrel, and put on plug at 230', through the dump bailer, and let set over-
night. Next morning hole was bailed dry, and 20 sacks of cement was added to
the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 2/24/66

INV. NO 2996-W

15.185-12693.0000

NOTICE

Correction on farm name.

The well plugging authority gave
the farm name on this well as the
Miller "B" # 2

It should have been the Mellies
"B" # 2, SE SW SE 36-21-12W
Stafford County

Archie Elving

Archie Elving