

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 24 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Southern States Oil Co

Complete Address Box 693 Great Bend, KS

Lease Name Tieperman A Well No. 3

Location C S/2 NE/SW Sec. 29 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3592

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 9:00 AM Day 21 Month 6 Year 1974

The above well was plugged as follows:

300 ft 8 5/8 surface cemented with 250 sacks. 3585 ft 5 1/2 long string  
cemented with 250 sacks. Open hole. Sand to 1746 ft, 5 sacks cement  
with bailer. Pulled 425 ft 4" & 375 ft 5 1/2. Set 10 ft rock bridge  
at 240 ft., 30 sacks cement. Mud to 40 ft, 10 ft rock bridge, 10  
sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 6/24/74

INV. NO. 9381-w