

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Virginia Drilling Company, Inc.  
Complete Address: 712 Brown Bldg., Wichita, Kansas  
Lease Name Ahlgrim Well No. # 1  
Location SE NE NE Sec. 29 Twp. 21 Rge. 12 (E) (W) W  
County Stafford Total Depth 3670'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X  
Other well as hereafter indicated:     
Plugging Contractor: Virginia Drilling Company, Inc.  
Address: 712 Brown Bldg., Wichita, Kansas License No.                               
Operation Completed: Hour 6:00PM Day 29th Month Oct. Year 1965

The Above well was plugged as follows:

279' of 8 5/8" surface pipe, cement circulated. Fluid in the hole was  
at 90'. 1st cementing plug and 1/4 sack of hulls was pushed in fluid to  
260', and cemented with 25 sacks, through the drill pipe. Hole was  
filled with drilling mud to 40', 2nd cementing plug, bridged solid  
with dry cement and hulls on fluid at 40', and cemented with 10 sacks  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.  
    
  

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 11/1/65  
INV. NO. 2069-U

Signed: Archie Elving  
Well Plugging Supervisor