

15.185.12590.0000

Form CP-3
Rev. 6-4-68

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sitrin Petroleum Corp.

Complete Address Box 693 Great Bend, Ks

Lease Name Teiperman A Well No. 8

Location NW/SE/SW Sec. 29 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3651

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Gasing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:30 AM Day 21 Month 5 Year 1971

The above well was plugged as follows:

290 ft of 8 5/8 surface pipe cemented, circulated. 3651 ft of 5 1/2
long string cemented with 150 sacks. Top perf. 3598 ft. Sand back
to 3575 ft, 5 sacks cement with bailer. Pulled 1806 ft of 5 1/2. Set
10 ft rock bridge at 250 ft. Fill hole with 4 yds of redimix to
surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell B. Bickert*
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 3739-W