

15.185.12335.0001

Form CP-3
Rev. 6-4-68

KANSAS

JL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sitrin Petroleum Corp.

Complete Address Box 693 Great Bend, Ks 67530

Lease Name H. Ahlgrim Well No. 1

Location C S/2 NW/NE Sec. 29 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 4074

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 5:00 PM Day 22 Month 5 Year 1971

The above well was plugged as follows:

310 ft 10 3/4 surface Cement circulated. 3952 ft of 4 1/2 long string
cemented with 800 sacks. Open hole. Sand back to 3925 ft, 4 sacks
cement with bailer. No pipe pulled. Set 10 ft rock bridge at
400 ft. in 4 1/2. Fill hole with 4 yds redimix to surface. 10 3/4
surface cemented solid.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell Bihantia*
Well Plugging Supervisor

INVOICE

DATE 5/25/71
INV. NO. 3753-W