


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 14 Twp. 21 Rge. 4 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Rex & Morris Drilling Company, et al.
Lease Name BULLER Well No. 1
Office Address Box 334, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 25, 1958
Application for plugging filed " 19 " "
Application for plugging approved " 19 " "
Plugging commenced " 19 " "
Plugging completed " 19 " "
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Box 180, Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	280'	10 3/4"	280	None
		0	584'	8 5/8"	584	431'
See attached log.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud from 3945' to 270'; Dumped 30 sacks cement on
bridge plug at 270'; Filled with mud to 40'; Set 10 sacks cement on
bridge plug at 40'; Filled to surface; Dumped 2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rex & Morris Drilling Company
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure
Box 334, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 19 58

My commission expires August 8, 1962.

Elizabeth Deschner,
Notary Public
Wichita, Kansas

PLUGGING
FILE SEC 14 T. 21 R. 4W
BOOK PAGE 141 LINE 34

11-4-58

RECEIVED
STATE CORPORATION COMMISSION
NOV 1958
CONSERVATION DIVISION
Wichita, Kansas

15.113.00446.0000

Elevation 1446 R.B.
1443 D.F.

BULLER WELL # 1

REX & MORRIS DRILLING COMPANY, ET AL.

TOTAL DEPTH:	3945	
CONTRACTOR:	Rex & Morris Drilling Co.	
COMMENCED:	10-14-58	Location: SW SW NW
COMPLETED:	10-25-58	Section 14-21S-4W
INITIAL PRODUCTION:	D. & A.	McPherson County, Kansas

Casing Record:
 10-3/4 @ 280' w/ 200 sacks
 8-5/8 @ 584' w/ 250 sacks
 (Pulled 430')

FORMATION	DEPTH
Surface Hole	280
Shale and Salt	550
Lime and Shale	740
Shale and Lime	1015
Lime and Shale	1190
Shale and Lime	1550
Shale	1890
Lime and Shale	2335
Shale and Sand	2585
Lime	2930
Lime and Shale	3142
Conglomerate	3257
Lime	3538
Shale	3701
Sand and Shale	3733
Shale and Lime	3796
Lime (Viola)	3820
Shale and Sand	3891
Lime T.D.	3945

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By: Paul D. Koontz
Paul D. Koontz, Geologist

STATE OF KANSAS
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 3rd day of November, 1958.

Elizabeth Deschner
Elizabeth Deschner, Notary Public

My commission expires: 8-8-62

PLUGGING
 FILE SEC. 14 T. 21 R. 4W
 BOOK PAGE 141 LINE 34

RECEIVED
 NOV 4 1958
 STATE DEPARTMENT COMMISSION
 GEOLOGICAL DIVISION
 WICHITA, KANSAS