

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-097-20373 - 0000

LEASE NAME Einsel

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

4620 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC. 12 TWP. 28S RGE. 18W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY Kiowa

PHONE # () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 2/77

Character of Well Gas (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 12/14/95

Plugging Completed 12/15/95

The plugging proposal was approved on _____ (date)
by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ TD _____

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put	Pulled out
				8 5/8	443	
				5 1/2	4805	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

12/14 Mixed 25 sx w/100# hulls. Started displacement, 113 bbls. 12/15 Mixed 4 sx gel, 50 sx cement & displaced w/6 sx gel & 3 bbls wtr @ 1160'. Pulled csg to 460' & mixed 50 sx cement. Pulled csg & topped off w/10 sx.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606

Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M Jack
(Address) Wichita, KS

RECEIVED
STATE CORPORATION COMMISSION
12-26-95

SUBSCRIBED AND SWORN TO before me this 22 day of Dec., 19 95



Kerran Redington
Notary Public - Kerran Redington

DRILLERS LOG

#1 EINSEL
 C NE NE Section 12-28S-18W
 Kiowa County, Kansas

OPERATOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

COMMENCED: January 15, 1977

COMPLETED: February 5, 1977

CASING RECORD: 8-5/8" @ 443' w/375 sx
 5-1/2" @ 4805' w/1600 gal. latex

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	400	Sand and shale
400	970	Shale
970	1680	Shale and shells
1680	1835	Shale
1835	2060	Shale and shells
2060	2370	Lime
2370	3390	Lime and shale
3390	3520	Lime
3520	3940	Lime and shale
3940	4759	Lime
4759	4800	Chert and shale
4800	4815	Shale and sand
4815		Rotary total depth

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.


 Don Gardner

Subscribed and sworn to before me this 24th day of February, 1977.

My appointment expires:
 January 4, 1981

Kathleen L. Butler
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

DEC 2 5 1995

FOR STATE CORPORATION COMMISSION
 WICHITA, KANSAS