

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-097-214240000
LEASE NAME Dirks
WELL NUMBER 1-30

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1980 Ft. from South Line of Section
460 Ft. from West Line of Section

LEASE OPERATOR Cross Bar Petroleum, Inc. SPOT LOCATION 200' West of Nw Sw
ADDRESS 151 N. Main, Suite 630 Section 30 Township 28s Range 18W
CITY, STATE, ZIP Wichita, Kansas 67202 County Kiowa
PHONE # 316-265-2279 Date Well Completed May 31, 1997
Character of Well Dry and Abandoned Date Plugging Commenced May 31, 1997
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed May 31, 1997

The plugging proposal was approved on May 27, 1997 at 8:15 am (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 5100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	275	and		
Redbeds	Shale	275	515	8-5/8"	500.39	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with heavy mud from 5100' to 635', then 80 sacks at 635'
10 sacks at 40', 15 sacks in the rathole and 10 sacks in the mousehole. Plugged
with 60/40 Poz, 6% Gel. Plug down at 8:00 am on 5-31-97 by Allied, Ticket
5549. Received plugging orders at 8:15am on 5-27-97 from Steve Middleton.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cross Bar Petroleum, Inc. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 3rd day of June, 19 97



[Signature]
(Notary Public)

6-4-97
RECEIVED
KANSAS CORP COMM
1997 JUN 4 A 1:04

My Commission Expires: _____

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG**Dirks 1-30**

LOCATION: 200' West of Nw Sw Section 30 T 28s R 18s W
API: 15-097-214240000 Kiowa County, Kansas

OWNER: Cross Bar Petroleum, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 21-May-97
COMPLETED: 31-May-97

TOTAL DEPTH: **DRILLER** 5100 FEET
LOGGER 5103 FEET

LOG

0 - 275 FEET Top Soil and Sand
275 - 515 FEET Shale
515 - 5100 FEET Shale, Limestone and Chert

CASING RECORDS

Spud @ 8:00 am on 5-21-97. Drilled 12-1/4" hole to 515'. Ran 12 joints of 23# 8-5/8" surface casing 500.39' set at 512' KB. Cemented with 265 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 6:15 pm on 5-21-97 by Allied. Good returns. Ticket # 6532.

Plugged well with heavy mud from 5100' to 635', then 80 sacks at 635' 10 sacks at 40', 15 sacks in the rathole and 10 sacks in the mousehole. Plugged with 60/40 Poz, 6% Gel. Plug down at 8:00 am on 5-31-97 by Allied, Ticket # 5549. Received plugging orders at 8:15am on 5-27-97 from Steve Middleton.

DEVIATION SURVEYS

1/2 degree(s) at 500 feet
1 degree(s) at 4493 feet
1/2 degree(s) at 5100 feet

6-4-97
RECEIVED
KANSAS CORP COMM
JUN 11 11:04