

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-185-21,490-0000 (of this well) 7/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Midwestern Supply Company, Inc. OPERATORS LICENSE NO. 8778
ADDRESS 300 Patton Road
Great Bend, Kansas, 67530 PHONE # (310)-793-8521

LEASE (FARM) Fisher WELL NO. 1 WELL LOCATION 150' W, NW SW NW COUNTY Stafford
SEC. 17 TWP. 21s RGE. 13w or (W) TOTAL DEPTH 3669' PLUG BACK TO _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 285' CEMENTED WITH 225 SACKS

CASING SIZE 5 1/2" SET AT 3663' CEMENTED WITH 100 SACKS

PERFORATED AT 3482-94 & 3509-12

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Will plug according to the rules & regulations of the State of Kansas

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

Bob Brentlinger w/Midwestern Supply Co., Inc. PHONE # (310)-793-8521
ADDRESS 300 Patton Road
Great Bend, Kansas, 67530 7-28-86

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. 60506/87 JUL 28 1986

ADDRESS P.O. Box 347
Chase, Kansas, 67524 PHONE # (310)-938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: 7-25-86

①

15.185 21490.0000

LAURIER RESOURCES (U.S.) INC.
#400555 4TH AVE. S. WEST
CALGARY ALBERTA, CANADA T2P3E7
CONTR H-30, INC.

REPLACEMENT CARD: 17-21-13W
#1 FISHER 150'W, NW SW NW

CTY STAFFORD

GEOL _____ FIELD HAZEL WEST

E 1925 KB CM 12/26/81 CARD ISSUED 3/4/82 IP OIL WELL
1920 GL LKC 3482-3512 OA

API 15-185-21,490

+	+	+
.	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
HEEB		3215	-1290
BR LM		3336	-1411
LANS		3348	-1423
B KC'		3566	-1641
VIOLA		3575	-1650
SIMP		3603	-1678
ARB		3658	-1733
RTD		3669	-1744

8 5/8" 285/225sx; 5 1/2" 3663/100sx

DST (1) 3346-3428(LKC)/30-60-60-90,
GTS/30", TSTM, REC 50'SGCM, SIP
698-681#, FP 76-76/61-61#
DST (2) 3432-45(LKC)/30-60-60-90,
450'SW, SIP 899-882#, FP 67-109/
126-202#
DST (3) 3467-3505(LKC)/30-60-60-90,
120'MO, 75'OCM, SIP 367-351#,
IFP INVALID/117#

INFO RELEASED: 5/13/82:
WAS TIGHT HOLE - OIL
WELL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

(OVER)

LAURIER RESOURCES (U.S.) INC. #1 FISHER 17-21-13W
150'W, NW SW NW

DST (4) INTV NA (LKC) / MISRUN
DST (5) 3506-55(LKC)/30-60-60-90, 60'GIP, REC 120'SOCMW,
SIP 336-336#, FP 62-62/78-92#
DST (6) 3556-65(LKC, PENN)/30-60-60-90, 60'GIP, REC 300'
SOCM, SIP 936-920#, FP 132-148/187-234#
DST (7) 3555-3669(LKC, PENN, SIMP, ARB)/30-60-60-90, REC 420'
OCM (25% OIL), 720'SOCM (15% OIL), SIP 913-905#, FP
140-352/445-749#
MICT - CO, PF(LKC) 24/3482-94, 6/3509-12, AC 1500G (15%NE),
SWB LD W/SO, POP

RECEIVED
STATE CORPORATION COMMISSION
CONS DIV WICHITA, KS

JUL 28 1986

Schlumberger

PERFORATING DEPTH CONTROL

COUNTY FIELD LOCATION WELL COMPANY

COMPANY LAURIER RESOURCES

WELL FISHER #1

FIELD HAZEL WEST

COUNTY STAFFORD STATE MISSISSIPPI

RECEIVED
 MISSISSIPPI COMMISSION
 JUN 2 1923

Location NW SW NW
 Sec. 17 Twp. 21S Rge. 13W

Other Services:
 HTI 3/4

Permo Datum: GROUND LEVEL; Elev.: 1920
 Log M d From HB 5 Ft. Above Perm. Datum
 Drillin red From KB

Elev.: K.B. 1925
 D.F. 1923
 G.L. 1920

Date	3-3-92
Run No.	ONE
Type Log	GAMMA RAY
Depth - Drill	3658
Depth - Logge	3663
Bottom logged interval	3660
Top logged interval	3690
Type fluid in hole	WATER OIL
Salinity, PPM Cl.	
Density	
Level	
Max. rec. temp., deg F.	
Operating rig time	1 HOUR
Recorded By	KRUCKENBERG
Witnessed By	THOMPSON

BORE-HOLE RECORD			CASING RECORD			
Bit Size	From	To	Size	Wgt.	From	To
7 7/8			8 5/8		SURE	292
			5 1/2	140	SURE	TD

The well name, location and borehole reference data were furnished by the customer.

FOLD HERE



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Darby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

GCT 28 '86

July 28, 1986

EXPIRES

WELL PLUGGING NOTICE

Fisher #1
150'W NW SW NW
Sec. 17-21S-13W
Stafford County

Midwestern Supply Company, Inc.
300 Patton Road
Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).