

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kiowa County, Sec. 2 Twp. 30S Rge. 18W(E) (W)

Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4
Lease Owner K & E Drilling, Inc.
Lease Name Fincham "A" Well No. 1
Office Address 719 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 20 19.68
Application for plugging filed February 20 19.68
Application for plugging approved February 20 19.68
Plugging commenced February 20 19.68
Plugging completed February 20 19.68
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4935 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	413'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 375' - Solid bridge and 25 sx. cement. Heavy mud up to 40' - Solid bridge and 10 sx. cement. 2 sx. cement in rat hole.

Job completed at 1:30 P.M.

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, H. L. Wilson (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Wilson
719 Union Center, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1968

My commission expires 9-14-70

Judie K. Eby
Notary Public.

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center
Wichita, Kansas 67202

WELL NAME: #1 Fincham "A"
LOCATION: C SW SW
Sec. 2-30S-18W
Kiowa County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: February 7, 1968

CASING RECORD:
8-5/8" @ 413' w/300 sx.

COMPLETED: February 20, 1968

ROTARY TOTAL DEPTH: 4935'

ELEVATION: 2068' Grd.; 2074' D.F.
2077' K.B.

PRODUCTION: Dry

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Soil - Rock	55
Blue Shale	300
Sand	335
Shale	380
Anhydrite	393
Shale	1282
Shale & Shells	1850
Shale & Lime	2168
Lime	4900
Lime & Chert	4935

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1968
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson H. L. Wilson

Subscribed and sworn to before me this 26th day of February, 1968.

My Commission expires: 9-14-70

Judie K. Eby
Judie K. Eby Notary Public.

