

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kiowa County, Sec. 7 Twp. 30 Rge. 17 (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Messman-Rinehart Oil Company
Lease Name Kane Ranch "G" Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 10 19 56
Application for plugging filed December 11 19 56
Application for plugging approved December 12 19 56
Plugging commenced December 12 19 56
Plugging completed December 12 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4994 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	392'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud from 4994' to 300'. Bridging plug and 20 sacks cement set at 300'. Hole filled with heavy rotary mud to 35'. Bridging plug and 10 sacks cement set at 35' to surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Messman-Rinehart Oil Company
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
518 Petroleum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 56

Elaine M. Malone

My commission expires September 5, 1960

Notary Public.

PLUGGING
FILE SEC 7 T 30 R 17 W
BOOK PAGE 125 LINE 16

NO. 1 KANE RANCH "G"Well Record

Location: SW SW SW, 7-30S-17W
Kiowa County, Kansas

Commenced: November 24, 1956

Operator: Messman-Rinehart Oil Company
518 Petroleum Building, Wichita, Kansas

Completed: December 10, 1956

Elevation: 2007 KB

Contractor: Messman-Rinehart Oil Company
518 Petroleum Building, Wichita, Kansas

Production: D & A

Casing Record: 8 5/8" @ 392' w/225 sacks cement.

* * * L O G * * *

Sand-clay	70
Shale	281
Anhydrite	300
Red Bed	660
Shale	911
Anhydrite	928
Shale	1420
Shale-lime	2291
Lime	2385
Lime-shale	3070
Shale-lime	3332
Lime-shale	3410
Shale-lime	3554
Lime-shale	3667
Shale-lime	3695
Lime-shale	3756
Lime	3820
Lime-shale	4035
Shale-lime	4140
Lime-shale	4210
Lime	4275
Lime-shale	4325
Lime	4683
Lime-shale	4800
Lime	4862
Lime-shale	4947
Lime-shale-chert	4987
Shale-lime	4994 R.T.D.

Electric Log Tops:

Heebner	4020 (-2013)
Br. Lime	4180 (-2173)
Lansing-Kc	4196 (-2189)
B/Kc	4553 (-2546)
Cherokee	4736 (-2729)
Mississippi	4833 (-2826)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland

Subscribed and sworn to before me
this 14th day of December, 1956.

Elaine M. Malone
Notary Public

PLUGGING		RECEIVED
FILE SEC 7 T 30 R 17W	BOOK PAGE 125 LINE 1620	STATE CORPORATION COMMISSION
		DEC 18 1956
		SERVATION DIVISION
		Wichita, Kansas

My Commission Expires: September 5, 1960