

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kiowa County. Sec. 6 Twp. 30S Rge. (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines NE SW SE  
Lease Owner Grahamart-Miller Oil Company  
Lease Name Kane Ranch "L" Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 17 19 56  
Application for plugging filed October 17 (Verbal) 19 56  
Application for plugging approved October 17 (Verbal) 19 56  
Plugging commenced October 17 19 56  
Plugging completed October 17 19 56  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5015' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	284	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy rotary mud from 5015' to 275'. Bridging plug and Halliburton plug set @ 275' w/ 20 sacks cement. Hole filled from this plug to 35' with heavy rotary mud. Bridging plug and Halliburton plug set @ 35' with 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company  
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. A. Gilliland (employee of owner) or (Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland  
518 Petroleum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 56

Elaine M. Malone Notary Public.

My commission expires September 5, 1960

PLUGGING  
FILE SEC 6 T. 30 R. 17W  
BOOK PAGE 108 L. I. E. 19

RECEIVED  
CORPORATION COMMISSION

20724 258  
CONSERVATION DIVISION  
Wichita, Kansas  
10-24-56

NO. 1 KANE RANCH "L"WELL LOG

Location: NE SW SE 6-30S-17W  
Kiowa County, Kansas

Commenced: September 22, 1956

Operator: Gramehart-Miller Oil Company  
518 Petroleum Bldg. Wichita, Kansas

Completed: October 17, 1956

Elevation: 2092 KB

Contractor: Messman-Rinehart Oil Company  
518 Petroleum Bldg. Wichita, Kansas

Production: D & A

Casing Record: 8 5/8" @ 284' w/225 sacks cement

\*\*\* L O G \*\*\*

Clay-shale	40
Shale	396
Anhydrite	406
Shale	1012
Anhydrite (top 1012)	1025
Shale & Red Bed	1145
Shale	1985
Shale-lime	2288
Lime-shale	2574
Lime	2740
Shale-lime	2777
Shale & iron	2786
Lime-shale	2857
Shale-lime	2985
Shale	3130
Shale-lime	3516
Lime-shale	3545
Shale-lime	3774
Lime	3818
Shale-lime	3915
Lime-shale	3973
Lime	4021
Shale-lime	4133
Lime-shale	4253
Lime	4907
Lime-Mississippi chert	4920
Chert	4963
Lime	4976
Mississippi chert	5015 R.T.D.

## Log Tops:

Heebner	4086 (-1994)
Br. Lime	4524 (-2162)
Lansing	4270 (-2178)
B/Kc	4631 (-2539)
Cherokee	4810 (-2819)
Miss.	4911 (-2819)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART OIL COMPANY


By: 

J. A. Gilliland

Subscribed and sworn to before me this 22nd day of October, 1956.

Elaine M. Malone  
Notary Public

My Commission Expires: September 5, 1960



RECEIVED  
CORPORATION COMMISSION  
OCT 24 1956  
CONSERVATION DIVISION  
Wichita, Kansas