


WELL PLUGGING RECORD

Give All Information Completely
No. Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County, Sec. 5 Twp. 30S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C NE/4 NE/4
Lease Owner K & E Drilling, Inc.
Lease Name Kane-Barstow Well No. 1
Office Address 719 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-3 19 66
Application for plugging filed 12-3 19 66
Application for plugging approved 12-3 19 66
Plugging commenced 12-3 19 66
Plugging completed 12-3 19 66
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4915 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	413	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud up to 400', plug and solid bridge @ 400'; 25 sx. cement above bridge. Heavy mud to 40'. Solid bridge @ 40', cement (10 sx) to base of cellar. Plugged rathole with 2 sx. cement. Plugging complete @ 10:30 A.M.

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.
Address 719 Union Center Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne L. Brinegar of K & E Drilling, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne L. Brinegar
719 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of December, 19 66

Judith K. Eby
Judith K. Eby Notary Public.

My commission expires 9-14-70

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center Building
Wichita, Kansas 67202

WELL NAME: Kane-Barstow #1
LOCATION: C NE NE Sec. 5-30S-17W
Kiowa County, Kansas

CONTRACTOR: **K&E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: 11/18/66
COMPLETED: 12/2/66
ELEVATION: 2110' Gr., 2116' DF,
2119' KB
PRODUCTION: D & A

CASING RECORD:
8-5/8" @ 413' w/300 sx.
ROTARY TOTAL DEPTH: 4915'

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Shale	65
Sand	95
Shale	402
Anhydrite	420
Shale	525
Shale & Shells	2032
Shale	2240
Lime & Shale	2315
Lime	2420
Shale & Lime	2645
Lime	2770
Shale & Lime	3205
Shale, Lime & Chalk	3390
Shale & Lime	3460
Lime	3625
Shale & Lime	3770
Lime	4157
Lime & Shale	4240
Lime	4841
Lime & Chert	4890
Lime	4915

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1966
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinegar, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Wayne L. Brinegar
Wayne L. Brinegar
Subscribed and sworn to before me this 6th day of December, 19 66.

Judie K. Eby
Judie K. Eby Notary Public.
My Commission expires: 9-14-70

