


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KIOWA County, Sec. 36 Twp. 30S Rge. 16W (E) (W)
Location as "NE/CNW/SW" or footage from lines 1250' S of N Line
Lease Owner GULF OIL CORP. 1250' E of W Line
Lease Name ROBBINS Q Well No. 1
Office Address BOX 9607, OKLAHOMA CITY, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 10-21 1961
Application for plugging filed 10-21 1961
Application for plugging approved 10-21 1961
Plugging commenced 10-21 1961
Plugging completed 10-21 1961
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. LECAMP, R. R. #1, STAFFORD, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed, Anhy. & Lime	Surface Cag.	-0-	412'	8-5/8"	412'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled hole with heavy mud - 4790' to 400'.
Set plug using 1/2 sk. hulls, Halliburton
Plug and 45 sx. cement through drill pipe
by Halliburton. Filled hole with mud up to
40'. Set bridge using 1/2 sk. hulls,
Halliburton Plug and 15 sx. cement to
cellar zero.

Job Completed: 3 p.m. - 10/21/61

RECEIVED
OCT 23 1961
CONSERVATION DIVISION
WICHITA, KANSAS

10-25-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. T. HONAKER, DRIG. SUPT. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.T. Honaker C. T. HONAKER, DRIG. SUPT.
BOX 232, RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of OCTOBER, 19 61

My commission expires 10-17-63

Leroy Dietz
Notary Public.

GULF OIL CORP. - Operator

SIERRA PETROLEUM CO., INC - Contractor

ROBBINS Q-#1
1250' S Of N Line
1250' E Of W Line
Sec. 36-30S-16W
Kiowa County, Kansas

T. D.: 4790'

Commenced: 10-5-61
Completed: 10-21-61

Casing:

8-5/8" Set at 412' K.B.

Cement:

with 150 sx. cement

FORMATION

DEPTH

Red Bed	132
Anhydrite	140
Lime	412
Red Bed & Shale	980
Shale, Shells & Gypsum	1200
Salt, Shale & Shells	1445
Shale & Shells	2077
Lime & Shale	4150
Lime	4659
Conglomerate	4666
Lime	4705
Kinderhook	4790

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

37
COMMISSIONER
OCT 24 1961
COUNTY CLERK
RUSSELL COUNTY

I hereby certify that the above information is true
and correct to the best of my knowledge.

C. T. Hankins

Subscribed and sworn to before me this 24th day of October,
1961.

[Signature]
Notary Public

My commission expires: 10-17-63