


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County. Sec. 18 Twp. 30 Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Barbara Oil Company
Lease Name Rice Well No. 1
Office Address 322 Central Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 17, 1957
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced January 17, 1957
Plugging completed January 17, 1957
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	373'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy rotary mud from 4734' to 360'. Bridging plug and 1/2 sx. hulls and 20 sxs. cement set at 360'. Hole filled with heavy rotary mud to 40'. Bridging plug and 1/2 sx. hulls and 10 sxs. cement set at 40' to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company
Address 518 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. A. Gilliland
518 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1957

Elaine M. Malone Notary Public.

My commission expires September 5, 1960

PLUGGING
FILE SEC 18 T 30 R 16W
BOOK PAGE 135 LINE 5

RECEIVED
CORPORATION COMMISSION
JAN 23 1957
1-20-57
CONSERVATION DIVISION
Wichita, Kansas

NO. 1 RICEWell Record

Location: NE SW SW, 18-30S-16W
Kiowa County, Kansas

Commenced: December 13, 1956

Operator: Barbara Oil Company
322 Central Bldg., Wichita, Kansas

Completed: January 17, 1957

Elevation: 1884 KB

Contractor: Messman-Rinehart Oil Company
518 Petroleum Bldg., Wichita, Kansas

Production: D & A

Casing Record: 8 5/8" @ 373' w/225 sacks cement.

* * * L O G * * *

Clay	60
Shale	750
Red Bed - shale	1400
Shale-lime streaks	1830
Lime-shale	2190
Lime-shale streaks	2309
Lime-shale	2535
Shale-lime	3059
Lime-shale	3190
Shale-lime	3395
Lime	3447
Shale-lime	3717
Lime	3866
Lime-shale	3988
Shale-lime	4088
Lime	4155
Lime-shale	4199
Lime	4257
Lime-shale	4297
Lime	4450
Lime-shale	4501
Lime	4589
Lime-shale	4652
Lime	4685
Lime chert	4730
Viola	4734 R.T.D.

Electric Log Tops:

Heebner	3887 (-2003)
Br. Lime	4054 (-2170)
Lansing	4073 (-2189)
Conglomerate	4635 (-2751)
Kinderhook	4668 (-2784)
Viola	4725 (-2841)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART OIL COMPANY

By: 

Subscribed and sworn to before me
this 24th day of January, 1957.

Elaine M. Malone
Notary Public

My Commission Expires: September 5, 1960

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1957

REGISTRATION DIVISION
Wichita, Kansas

PLUGGING	
SEC	18 T. 30 R. 16 W
BOOK	PAGE 135 LINE 5