


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County, Sec. 36 Twp. 21S Rge. 12W (W) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW SW SE
Lease Owner Petroleum, Inc. & J. D. Drilling Co., Inc.
Lease Name Mellies 'B' Well No. 3
Office Address 305 East Third, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 2, 19.52
Application for plugging filed July 2, 19.52
Application for plugging approved July 2, 19.52
Plugging commenced July 2, 19.52
Plugging completed July 2, 19.52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced?..... Yes

Name of Conservation Agent who supervised plugging of this well..... Mr. M. A. Rives
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 361.7 Feet
Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Mudded up to 240' and set wooden plug at 240'.
Cemented and displaced 15 sacks cement through
drill pipe onto plug at 240'. Mudded up to 35'
and placed 1/2 sack hulls followed by wooden
plug set at 35'. Filled hole to bottom of well
cellar with 10 sacks cement.

RESERVATION
7-22-52

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor..... J. D. Ferrell Drilling Co., Inc.
Address..... Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W W Fisher
305 East Third, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of July 1952
Shirley Heidman
Notary Public.

My commission expires October 13, 1954
23-8390-s 6-51-20M

FILED
36-21S-120
BOOK PAGE 28-28

WELL LOG

Petroleum, Inc.
Derby Building - 3rd and Broadway
Wichita, Kansas

Mellies "B" #3
SW/4 SW/4 SE/4
Section 36-21S, 12W,
Stafford Cty, Ks.

Total Depth: 3617'
Commenced: 6/20/52 Completed: 7/3/52
Contractor: J. D. Ferrell Drilling Co., Inc.
Elevation: 1812 K. B.
Rotary: 0 - 3617'

Casing Record: 251.42' of 8 5/8" 24# Casing (8 jts.); cemented
175 sacks bulk cement and 2 sacks calcium chloride;
cement circulated. HOWCO.

Figures Indicate Bottoms of Formations:

Cellar	0 - 5
Clay and Sand	5 - 70
Shale and Sand	70 - 140
Red Bed, Shale & Shells	140 - 249
Red Bed and Shells	249 - 510
Sand and Shale	510 - 580
Anhydrite	580 - 605
Shale and Shells	605 - 1210
Shale, Lime and Shells	1210 - 1460
Shale and Shells	1460 - 1490
Broken Lime	1490 - 1570
Lime and Shale	1570 - 1600
Sandy Lime	1600 - 1650
Shale and Lime	1650 - 1785
Broken Lime	1785 - 1870
Sandy Lime	1870 - 1940
Lime and Shale	1940 - 2070
Broken Lime	2070 - 2135
Shale and Shells	2135 - 2835
Shale and Lime	2835 - 2970
Shale and Shells	2970 - 3015
Lime	3015 - 3100
Shale and Lime	3100 - 3170
Shale, Lime and Shells	3170 - 3240
Lime	3240 - 3414
Lime and Shale	3414 - 3465
Lime	3465 - 3495
Lime and Chert	3495 - 3550
Shale	3550 - 3599
Arbuckle Lime	3599 - 3603
Lime	3603 - 3617 T. D.

Tops:


Heebner	3082 -1270
Brown Lime	3215 -1403
L. Kansas City	3241 -1429
Viola	3508 -1696
Simpson	3543 -1731
Arbuckle	3599 -1787
Total Depth	3617 -1805

We hereby certify this to be a correct and accurate log of the above-described well as shown on the Daily Drilling Reports.

J. D. FERRELL DRILLING CO., INC.

J. D. Ferrell

Subscribed and sworn to before me this 17th day of July, 1952.



Emma Jean [Signature]
Notary Public
RATON COMMISSION

commission expires August 29, 1955.

JUL 22 1952

CONSERVATION DIVISION
Wichita, Kansas