


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 36 Twp. 21 Rge. 12 (X) (W)

Location as "NE/CNW/SW" or footage from lines. SE SW NE  
Lease Owner Buick Drilling Inc.  
Lease Name Mellies Well No. 1  
Office Address P.O. Box 331, St. John, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 19, 1953  
Application for plugging filed November 19, 1953  
Application for plugging approved November 19, 1953  
Plugging commenced November 19, 1953  
Plugging completed November 19, 1953  
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	265	8 5/8"	265'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3601 feet to \_\_\_\_\_ feet for each plug set.

3601 back to 240 feet heavy rotary mud. One plug with 20 sacks cement.  
240 feet back to 40 feet, One plug with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buick Drilling Inc.  
Address P. O. Box 331, St. John, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.  
H. R. Buick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P. O. Box 331, St. John, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of November, 1953

[Signature]  
Notary Public.

My commission expires December 26, 1955

**PLUGGING**  
FILE SEC 36 T 21 R 12W  
BOOK PAGE 144 LINE 22

11-23-53

## DRILLERS LOG

Mellies #1  
 Commenced R.D.: 10-24-53  
 Completed R.D.: 11-19-53  
 Total Depth: 3601'  
 Casing Record: 265' of 8 5/8"

SE SW NE, Sec. 36-21-12  
 Stafford County, Kansas  
 Elevation: 1794 D.F.  
 Initial Prod.: Arbuckle  
 Contractor: Buick Drilling Inc.

STRATA	DEPTH
Clay and Sand	0 - 170
Red Clay and Sand	170 - 218
Red Bed	218 - 265
Red Bed and Shale	265 - 370
Red Bed, Shale and Shells	370 - 555
Anhydrite	555 - 585
Shale, Shells, and Red Bed	585 - 725
Red Bed and Shells	725 - 1060
Red Bed and Shale	1060 - 1220
Salt and Shale	1220 - 1310
Shale and Shells	1310 - 1425
Lime and Shale	1425 - 1475
Lime	1475 - 1585
Lime and Shale	1585 - 3210
Lime	3210 - 3425
Lime and Shale	3425 - 3455
Lime	3455 - 3475
Shale and Lime	3475 - 3550
Lime	3550 - 3573
Lime and Shale	3573 - 3601 T.D.

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

*H. R. Buick*

H. R. Buick, President

Signed and sworn to in my presence this 20th day of November, 1953, by H. R. Buick, President of the Buick Drilling Inc.

*Roberta Shogren*  
 Notary Public

My Commission expires December 26, 1955.

