

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.185.13083.0000

LEASE NAME Hall

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

         Ft. from S Section Line

         Ft. from E Section Line

LEASE OPERATOR Kaiser-Francis Oil Co.

SEC. 20 TWP. 21S RGE. 12W (E) or (W)

ADDRESS P. O. Box 666 Ellinwood, KS 67526

COUNTY Stafford

PHONE (316) 564-3214 OPERATORS LICENSE NO. 6568

Date Well Completed         

Character of Well Oil

Plugging Commenced 12-03-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-09-96

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filled?          if not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3529'

Show depth and thickness of all water, oil and gas formations.

12-22-96

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	318'	none
				5 1/2	3524'	1821'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from          feet to          feet each section. Plugged off bottom with sand to 3463' & ran 5 sks cement. Shot at 2415', worked pipe free. Went to pull pipe next day, it was not free. Worked pipe. Shot at 2214, 2017, & 1821. Pipe came free at 1821'. Pulled all pipe. Plugged well with 300# hulls, 10 gal. 50 sks cement, 10 gal. 100# hulls. Pumped rest of cement (125 sks) down the surface pipe. Max pressure 500#. Shut in 100#. Plugging complete. 60/40 6%.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P. O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Co.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed is the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of December, 1996

*Gene Stenberg*  
Notary Public

My Commission Expires:         



WELL LOG

ANSCHUTZ DRILLING COMPANY, INC.

Hall #2, C N/2 N/2 NW/4 20-21-12  
Stafford County, Kansas

*Stafford*

COMMENCED: 12-15-49

COMPLETED: 12-28-49

0	230	Sand
230	285	Sand and Red Bed
285	330	Red Bed
330	650	Red Bed
650	675	Red Bed
675	700	Anhydrite
700	1010	Shale and shells
1010	1315	Shale and shells
1315	1390	Salt and shale
1390	1450	Shale and shells
1450	1500	Shale and lime
1500	1585	Lime
1585	1715	Lime
1715	1820	Shale and shells
1820	1895	Lime Broken
1895	2045	Shale and lime
2045	2155	Shale and lime
2155	2285	Lime
2285	2320	Lime
2320	2350	Shale and lime
2350	2510	Shale and lime
2510	2645	Shale and lime
2645	2760	Shale and lime
2760	2845	Shale and lime
2845	2920	Lime and shale
2920	3010	Lime
3010	3075	Lime
3075	3160	Lime
3160	3237	Shale and lime
3237	3260	Lime
3260	3310	Lime
3310	3330	Lime
3330	3340	Lime
3340	3391	Lime
3391	3441	Lime
3441	3488	Lime and shale
3488	3529	Shale and lime
3529		Notary Total Depth

CASING RECEIVED

Set 318' of 8-5/8" surface casing with 200 sacks bulk cement

Set 5-1/2" at 3524', cemented with 150 sacks cement.

RECEIVED  
 JAN 29 1950  
 STAFFORD COUNTY, KANSAS  
 CLERK

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Hall #2 located C N/2 N/2 NW/4 20-21-12, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *H. R. Jensen*

Subscribed and sworn to before me this 3rd day of January, 1950.

*Martha Long*  
 Notary Public

My commission expires September 12, 1953