

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 5 Twp. 21 Rge. 11 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW SW SW

Lease Owner F. G. Holl  
Lease Name John Kasselmann #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67207  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7/21/71 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7/24/71 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3495 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8 4 1/2"	287 3494	none 2848'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3455', pushed plug to 3300' and dumped 5 sacks of cement. Shot pipe at 2853', worked pipe loose and pulled 84 joints. Set 5 sacks of cement overnight plug at 260. Bailed fluid down to Olug and dumped 4 yards ready mix.

Plugging Complete.




(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

Subscribed and Sworn to before me this 28th day of July, 19 71



Margaret Melcher  
Notary Public.

WELL LOG

Date Commenced: October 25, 1964  
 Date Completed: November 3, 1964

F. G. HOLL  
 "John Kasselman" # 1  
 NW SW SW Section 5-21s-11w  
 Stafford County, Kansas

ELEVATION: 1816 K.B.

0 - 150'	Sand & Clay
150 - 570'	Red Bed
570 - 590'	ANHYDRITE
590 - 1230'	Red Bed Shale Salt
1230 - 1460'	Shale Shells
1460 - 1685'	Shale & Lime
1685 - 2030'	Lime - Shale
2030 - 2700'	Shale & Lime
2700 - 3010'	Lime
3010 - 3014'	Shale
3014 - 3042'	Lime Shale
3042 - 3135'	Shale
3135 - 3155'	Brown Lime
3155 - 3400'	Lime
3400 - 3433'	Chert Shale
3433 - 3445'	Sand Shale
3445 - 3495'	Dolomite

FORMATION DATA

Heebner	3010	-1194
Brown Lime	3135	-1319
Lansing	3155	-1339
Conglom.	3400	-1584
Simpson Sd	3433	-1617
Arbuckle	3445	-1629
RTD	3495	-1679

SURFACE CASING: Set 8-5/8"  
 Casing at 287' with 225  
 sacks cement.

PRODUCTION CASING: Set  
 4 1/2" casing at 3494' with  
 75 sacks Pozmix with salt


AFFIDAVIT

STATE OF KANSAS  
 COUNTY OF BARTON ) ss.

L. O. Chubb of lawful age does swear that the facts and  
 statements herein contained are true and correct to the best of his  
 knowledge.

  
 L. O. Chubb

Subscribed and sworn to before me this 9th day of November, 1964.

  
 Clair E. Stinson  
 NOTARY PUBLIC

My Commission Expires:  
 June 24, 1967

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 14 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas