

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 E. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
1-31-03
JAN 31 2003

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-097-21477-0000
LEASE NAME Cullins
WELL NUMBER 2-30
3840 ft. from S Section Line
1320 ft. from E Section Line
SEC. 30 TWP. 28 RGE. 17 (E) or (W)
COUNTY Kiowa

KCC WICHITA

LEASE OPERATOR Vincent Oil Corporation
ADDRESS 125 N. Market St. #1075, Wichita, KS 67202
PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 11-6-01
Plugging Commenced 1/20/03
Plugging Completed 1/22/03

Character of well oil Gas (RSP/KCC 3-3-03)
(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 1/20/03 (date)
by Steve Durant (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Mississippian Depth to Top 4846 Bottom 4904 T.D. 4904

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 533 | none |
| | | | | 4 1/2" | 4904 | 3031 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___feet to ___feet each set

Sand at 4780, bailed 4 sacks cement. Shot pipe at 3109, 3031, worked free. Pulled to 1100, pump 12 sacks gel, 50 sacks cement. Pull to 560, pump 50 sacks cement, pull to 40 and pump 10 sacks cement. lay last jt. down.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Richard A. Hiebsch ~~(Employee of Operator)~~ or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.


(Signature) Richard A. Hiebsch
(Address) 125 N. Market, Suite 1075
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me 30th day of January, 2003

Yolanda Eubanks

Notary Public Yolanda Eubanks

My commission Expires :



Form CP-4
Revised 05-88

OR

ALLIED CEMENTING CO., INC. 12565

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine L.D.G.

| | | | | | | | |
|---|----------------|-----------------|----------------------------------|-----------------------------|------------------------------|----------------------------|------------------------------|
| DATE <i>1-22-03</i> | SEC. <i>30</i> | TWP. <i>28S</i> | RANGE <i>17W</i> | CALLED OUT <i>6:00 A.M.</i> | ON LOCATION <i>8:45 A.M.</i> | JOB START <i>9:10 A.M.</i> | JOB FINISH <i>10:30 A.M.</i> |
| LEASE <i>Cullin</i> | | WELL# <i>1</i> | LOCATION <i>Brenham Elevator</i> | | COUNTY <i>Kiowa</i> | STATE <i>KS</i> | |
| <input checked="" type="checkbox"/> OLD OR NEW (Circle one) | | | <i>1/2W 1 1/2S 1/4W S/INTO</i> | | | | |

CONTRACTOR *Quality*
 TYPE OF JOB *O.H.P.*
 HOLE SIZE *12 1/4* T.D. *1100*
 CASING SIZE *4 1/2* DEPTH *1100*
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TCOL DEPTH
 PRES. MAX *-* MINIMUM *-*
 MEAS. LINE SHOE JOINT *-*
 CEMENT LEFT IN CSG. *-*
 PERFS.
 DISPLACEMENT *Fresh H₂O*
 EQUIPMENT
 PUMP TRUCK CEMENTER *David W.*
 # *302* HELPER *Dwayne W.*
 BULK TRUCK
 # *240* DRIVER *Larry D.*
 BULK TRUCK
 # DRIVER

OWNER *Vincent Oil Co.*
 CEMENT
 AMOUNT ORDERED *110sx 60' 40' 6*
12st Gel
 COMMON *66* @ *6.65* *438.90*
 POZMIX *44* @ *3.55* *156.20*
 GEL *18* @ *10.00* *180.00*
 CHLORIDE @
 @
 @
 @
 @
 @
 @
 @
 HANDLING *128* @ *1.10* *140.80*
 MILEAGE *30* *153.60*
 RECEIVED
 JAN 31 2003 TOTAL *1069.50*

REMARKS:

KCC WICHITA SERVICE

*1st Plug at 1100 FT pump 12sx 60' pump
 50sx Cement Displace w/ 10 BDLs Fresh
 H₂O 2 1/4" Plug 560 FT pump 6 BDLs
 Fresh H₂O pump 50sx Cement Displace
 w/ 3 BDLs, Fresh H₂O at 40 FT
 pump lost cement to surface
 Wash up Rig Down Move OFF*

DEPTH OF JOB *1100*
 PUMP TRUCK CHARGE *475.00*
 EXTRA FOOTAGE @
 MILEAGE *30* @ *3.00* *90.00*
 PLUG @
 @
 @

TOTAL *565.00*

CHARGE TO: *Vincent Oil Co.*
 STREET
 CITY STATE ZIP

FLOAT EQUIPMENT

@
 @
 @
 @
 @

TOTAL

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX *111.15*
 TOTAL CHARGE *1745.65*
 DISCOUNT *163.45* IF PAID IN 30 DAYS

SIGNATURE *X Jim Mack X*

PRINTED NAME

net # 1582.20