


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 11 Twp. 30S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines C/SE NW
Lease Owner Time Petroleum Company
Lease Name Stockwell Well No. 1
Office Address 815 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 23 1963
Application for plugging filed July 23 1963
Application for plugging approved July 23 1963
Plugging commenced July 23 1963
Plugging completed July 24 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5334 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	320'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 240' with 20 sacks of cement and 1/4 sack of hulls; plugged at 40' with 10 sacks of cement and 1/4 sack of hulls. Plugged rathole with 2 sacks of cement and also put 2 sacks of cement in the mousehole. Job completed at 1:00 A. M. July 24, 1963.

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim B. McWilliams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams
Jim B. McWilliams
P. O. Box 355, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July 1963

My commission expires December 14, 1965
Elaine H. Taylor Notary Public.

INVOICED

DATE 7/26/63
INV. NO. 7497-4

D R I L L E R S L O G

#1 Stockwell

CASING RECORD: 312' new 8-5/8" surface casing
 COMPANY: Time Petroleum Company
 DESCRIPTION: C/SE NW Section 11-30S-20W Kiowa County, Kansas
 CONTRACTOR: Strata Drilling, Inc.
 TOTAL DEPTH: 5334'
 COMMENCED: July 8, 1963
 COMPLETED: July 24, 1963

RECEIVED
 STATE CORPORATION COMMISSION

JUL 26 1963

D. & A.

CONSERVATION DIVISION
 Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Clay and Sand	0	252	Ran 312' of new 8-5/8" surface casing; set and cemented at 320' with 275 sacks of regular cement, 2% gel and 3% C. C.. Plug down at 1:30 P. M. July 9, 1963. Cement circ..	
Red Bed	252	775		
Shale	775	1700		
Shale & Lime	1700	2450		
Lime	2450	2950		
Lime & Shale	2950	3710		
Lime	3710	4185		
Lime & Shale	4185	4395		
Lime	4395	4864		
Lime & Shale	4864	4905		
Lime	4905	5015		Ran one drill stem test:
Lime & Shale	5015	5059		
Lime, Chert & Shale	5059	5109		
Chert	5109	5111		Ran Schlumberger log.
Lime & Shale	5111	5200	D. & A.	
Chalky Lime & Shale	5200	5245		
Lime	5245	5334		

Total Depth 5334'

Plugged hole as follows: Plugged at 240' with 20 sacks of cement and 1/4 sack of hulls; plugged at 40' with 10 sacks of cement and 1/4 sack of hulls. Plugged rathole with 2 sacks of cement and also put 2 sacks of cement in the mouse-hole. Job completed at 1:00 A. M. July 24, 1963.

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
 Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 24th day of July, 1963.

Elaine H. Taylor
 Elaine H. Taylor, Notary Public

My Commission Expires:
 December 14, 1965