


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 30 Twp. 30S Rge. 18 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
approx C NE SW

Lease Owner Petroleum, Inc.
Lease Name Robbins 'L' Well No. 1
Office Address Suite 800, 300 W. Douglas, Wichita, Ks 672
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
dry hole



Locate well correctly on above
Section Plot

Date Well completed 11-30⁹ 80
Application for plugging filed 11-30¹⁹ 80
Application for plugging approved 11-30¹⁹ 80
Plugging commenced 11-30¹⁹ 80
Plugging completed 11-30¹⁹ 80
Reason for abandonment of well or producing formation
no commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
-- 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5165
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	196'	13-3/8	199	none
			600	8-5/8	592	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid to 600', plug, 50 sx
Fluid to 40', plug, 10 sx
Rat hole 10 sx

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
515 R.H. Garvey Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 19 80

My commission expires April 30, 1983

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 5 1980

CONSERVATION DIVISION
Wichita, Kansas

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

DRILLER'S LOG

PETROLEUM, INC.
 No. 1 Robbins 'L'
 Approx C NE SW
 Sec. 30-30S-18W
 Kiowa Co., Ks.

Commenced: 11-17-80
 Completed: 11-30-80

Surface Casing: 199' of 13 5/8"
 cmtd w/225 sx Class H, 2% gel, 3% cc;
 592' of 8-5/8" cmtd w/325 sx Class A,
 2% gel, 3% cc

FORMATIONDEPTH

Surface Hole	0 - 600
Sand & Shale	600 - 1204
Shale	1204 - 1610
Shale & Lime	1610 - 2260
Shale, Lime & Sand	2260 - 2460
Lime & Shale	2460 - 4000
Shale & Lime	4000 - 4150
Lime & Shale	4150 - 4350
Lime	4350 - 4627
Lime & Shale	4627 - 4718
Lime	4718 - 5165 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 3rd day of December 1980.

Dorothy L. Schmidt
 Dorothy L. Schmidt, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

DEC. - 5 1980

CONSERVATION DIVISION
 Wichita, Kansas

DOROTHY L. SCHMIDT
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Appt. Exp. April 30, 1983