


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 16 Twp. 30 Rge. 18 (EX) (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Elv Well No. 1
Office Address 522 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-25-59 19
Application for plugging filed 7-25-59 19
Application for plugging approved 7-25-59 19
Plugging commenced 7-25-59 19
Plugging completed 7-25-59 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5115 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	492'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Lay down D.P. Filled hole w/ mud to 300' - Halls -
Plug 20 sx cement thru D.P. Filled hole w/ mud to
35' - Halls - Plug cement to base of cellar -
1 sx cement in rathole - Tear down, Loadout

STATE COMMISSION
JUL 30 1959
7-30-59
CON. DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. F. Carter, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 59

My commission expires May 11, 1963

Marguerite Dickoy
Marguerite Dickoy
Notary Public.



CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Ely
C SE SE Section 16-30-18W
Kiowa County, Kansas

Elevation 2230 K.B.
Set 8 5/8" @ 492' w/ 250 sacks

Contractor: Rupp-Ferguson Oil Co.
Commenced: 7-7-59
Completed: 7-25-59

Figures Indicate Bottom of Formation

105	soil, clay and sand
255	clay
355	sand streaks
486	red bed
521	anhydrite
1052	red bed
1070	anhydrite
1300	shale
1950	shale and shells
2208	shale and lime streaks
2575	lime and shale
2579	lime streaks
2671	sandy lime and shale
3080	shale and lime
3131	shale with lime streaks
3176	shale and lime
3562	shale
3842	shale and lime
4120	lime
4220	lime and shale
4418	shale and sandy lime
4524	lime and shale
4609	lime
4665	lime and shale
4739	lime
5063	lime and shale
5115	Mississippian T.D.

RECEIVED
STATE OF KANSAS COMMISSION
JUL 30 1959
CO. DIVISION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, J. F. Carter, Jr., Petroleum Engineer for Rupp-Ferguson Oil Co., do hereby certify the above and foregoing to be a true and correct copy of the log of the No. 1 Ely well.

PLUGGING
FILE SEC. 16 T. 30 R. 18W
BOOK PAGE 56 LINE 28

J. F. Carter, Jr.
J. F. Carter, Jr.

Subscribed and sworn to before me this 29th day of July, 1959.

Marguerite Wickey
Notary Public