

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County, Sec. 5 Twp. 30 Rge. 18 ~~28~~ (W)

Location as "NE/CNW%SW%" or footage from lines C-SW-SW

Lease Owner Northern Natural Gas Producing Company

Lease Name Parkin "B" Well No. 6

Office Address 2223 Dodge St., Omaha, Nebraska

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 1, 1959

Application for plugging filed December 1, 1959

Application for plugging approved December 1, 1959

Plugging commenced 11.00 A. December 1, 1959


Plugging completed 4.30 P.M. December 1, 1959

Reason for abandonment of well or producing formation No productive zone for commercial oil or gas found.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5100 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	383	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 40 sx. cement 5100 to 4980  
Heavy mud 4980 to 380  
Rubber plug at 380  
Spotted 20 sx. cement 380 to 310  
Heavy mud 310 to 20  
Rubber plug 20  
Spotted 10 sx. 20 to bottom of cellar  
Cut pipe off 4 feet below ground level and welded cap on same

RECEIVED  
STATE CORPORATION COMMISSION  
12-29-59  
DEC 29 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 814 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Stevens, ss.  
Richard G. Schmidt (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard G. Schmidt

Box 607, Hugoton, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 21 day of December, 19 59

Gayle J. Cox  
Notary Public.

My commission expires 6-7-62



## PARKIN 6-B

C SW SW Sec. 5-30S-18W Kiowa Co., Ks.

Rig up Rotary Tools 11-10-59

Set 12 jts. 8 5/8" Casing @392.79'  
Cement W/280 sz. pozmix 2% C.C.

Tore Down Rotary Tools 12-1-59

FORMATION	FROM	TO
Sand & Clay	0	400
Redbeds	400	584
Shale & Lime	584	2515
Lime	2515	3182
Shale & Lime	3182	3980
Lime	3980	4250
Lime & Shale	4250	4420
Lime	4420	5100 T. D.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 13 1963

CONSERVATION DIVISION  
Wichita, Kansas