


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County. Sec. 5 Twp. 30 Rge. (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines C N/2 SE/4 SW/4  
Lease Owner Herman Geo. Kaiser, Oil Producer  
Lease Name Parlin D Well No. 1  
Office Address 909 Palace Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 3/18 19 60  
Application for plugging filed 3/18 19 60  
Application for plugging approved 3/18 19 60  
Plugging commenced 3/18 19 60  
Plugging completed 3/18 19 60  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	431	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH HEAVY ROTARY MUD TO 425 FT.,  
SET PLUG AND CEMENTED WITH 20 SACKS CEMENT  
AND 1/3 SACK HULLS THROUGH DRILL PIPE. MUDDIED HOLE  
TO 35 FT., SET PLUG AND CEMENTED WITH 1/3 SACK  
HULLS AND 10 SACKS CEMENT TO SURFACE.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 25 1960  
CONSERVATION DIVISION  
Wichita, Kansas

3 25 60

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Armer, Inc.  
Address 709 Petroleum Bldg. Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

L. C. Sponenberg (employee of contractor of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 60

My commission expires February 13, 1964


Rose Furey  
Rose Furey  
Notary Public.

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser, Oil Producer**  
FARM **Parkin D** NO. **1**

SEC. **5** T. **30** R. **18W**  
LOG. **C N 1/2 SE/4 SW/4**

TOTAL DEPTH **5041** COUNTY **Kiowa**  
COMM. **2/27/60** COMP. **3/19/60**  
SHOT OR TREATED  
CONTRACTOR **Armer, Inc.**  
ISSUED



CASING  
20 10  
15 8 **431'**  
12 6  
13 5

ELEVATION **2243 K. B.**  
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- Surface Clay 30'
- Sand 70'
- Shale 160'
- Shale & Shells 717'
- Sand 797'
- Shale & Shells 800'
- Shale, Shells & Bed Bed 1140'
- Anhydrite 1165'
- Red Bed, Shale & Shells 1375'
- Shale & Shells 2125'
- Shale & Lime 2460'
- Lime 2895'
- Lime & Shale 2950'
- Lime 3025'
- Lime & Shale 3795'
- Lime 3965'
- Lime & Shale 4370'
- Lime 4500'
- Lime & Shale 4535'
- Lime 4780'
- Lime & Shale 4945'
- Lime 4985'
- Lime & Shale 5011'
- Mississippi 5041'

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 25 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Formation Tops:

	<u>Sample</u>	<u>Electric Log</u>
Heebner	4175 -1932	4175 -1932
Douglas	4209 -1966	4206 -1963
Brown Lime	4357 -2114	4356 -2113
Lansing	4372 -2129	4371 -2128
Mississippi	4985 -2742	4984 -2741
Total Depth	5041 -2798	5040 -2797

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By L. C. Sponenberg  
L. C. Sponenberg

STATE OF KANSAS )  
                          ) SS..  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 23rd day of March, 1960.

Rose Furey  
Rose Furey, Notary Public

My Commission expires February 13, 1964.