


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
1001 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 4 Twp. 30S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Phillips Petroleum Company
Lease Name Parkin Well No. 1
Office Address Box 287 - Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 13, 19 62
Application for plugging filed February 14, 19 62
Application for plugging approved February 16, 19 62
Plugging commenced February 21, 19 62
Plugging completed February 24, 19 62
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production ===== 19 62
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Haebner</u>	<u>Dry</u>	<u>4146</u>		<u>8 5/8"</u>	<u>408'</u>	<u>None</u>
<u>Toronto</u>	<u>"</u>	<u>4168</u>		<u>4 1/2"</u>	<u>5054</u>	<u>2800'</u>
<u>Brown Lime</u>	<u>"</u>	<u>4326</u>				
<u>LKC</u>	<u>"</u>	<u>4341</u>				
<u>Base LKC</u>	<u>"</u>	<u>4706</u>				
<u>Marmaton</u>	<u>"</u>	<u>4732</u>				
<u>Cherokee</u>	<u>"</u>	<u>4892</u>				
<u>Mississippian</u>	<u>"</u>	<u>4970</u>				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set cast iron brige plug at 4530'. Plugged back from 4530' to 4500' with rock. Dumped 5 sx. cement to 4450'. Shot casing at 4408' - 4245' - 4083'. Pipe loose at 2787'. Mudded hole to 350'. Set rock bridge to 340'. Dumped 20 sx. cement to 280'. Mudded to 40' and set rock bridge to 30'. Dumped 10 sx. cement in filling to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1962

CONSERVATION DIVISION

2-27-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. E. Michael (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael
Box 287 - Gt. Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 62

My commission expires 11/18/65

Joseph M. Beal
Notary Public.

EXPLORATION RECORDLease ParkinWell 1

Formation Name	Top	Base	Remarks
Sand and Clay		40	
Shale and Sand		100	
Shale and Shells		345	
Shale		409	
Shale and Shells		1000	
Red Bed, Shale and Shells		1116	
Anhydrite		1147	
Shale and Shells		1200	
Shale and Lime		1460	
Shale and Shells		1835	
Shale and Lime		2310	
Lime and Shale		2330	
Lime		2580	
Lime and Shale		2680	
Shale and Lime		2810	
Lime and Shale		3045	
Shale and Lime		3210	
Lime and Shale		3890	
Lime		4155	
Lime and Sandy Shale		4210	
Shale and Lime		4350	
Lime and Shale		4505	
Lime		4755	
Lime and Shale		4855	
Lime		4955	
Lime and Shale		4970	
Lime		5055	

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1962

CONSERVATION DIVISION
Wichita, Kansas