

15.159.04211.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pat Simmons

Complete Address 5252 N. Broadway, Wichita, Kansas 67219

Lease Name Renollett Well No. 4

Location NW SE SW Sec. 5 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3535'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King, Hutchinson, Kansas License No. 4410

Operation Completed: Hour 10 AM Day 18 Month October Year 1969

The above well was plugged as follows:

Hole filled with sand to 3470' and cemented with 5 sacks cement.

Hole filled with mud to 185'. Rock bridge set from 185' to 175' and hole cemented

with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to

30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/20/69

INV. NO. 683-W