

KANSAS
COMMISSION
STATE CORPORATION
AUG 29 1950

DISTRICT CONSERVATION AGENT'S REPORT

RECEIVED
Conservation Div.

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 83-12

LOCATION NW-SW-SW

SEC. 5 TWP. 21 RGE. 6-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Bennett

Operator W.H.C. Bennett Address Box #31 Augusta - Kans -

Field _____ County Bies

Total Depth 3532 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 165 ft. Circulated with cement
5 1/2" casing set at 3490 ft - Plugged back to 3480 ft
with shot - 5 sacks of cement with Manup Bailey
at 3480 ft - Shot off & Pulled the 5 1/2" casing - Filled
with mud to 165 ft - Set Rock Bridge & 15 sacks of
cement at 165 ft. Mud to 35 ft - Bridge &
10 sacks of cement at the surface
A. & L. Pipe Pulling Co. - Plugging Contractors

PLUGGING
FILE SEC 5 T 21 R 6W
BOOK PAGE 23 LINE 18

C. M. Stough
District Conservation Agent

Date 8-28-50