


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 19 Twp. 21S Rge. 13 (W) W (W)
Location as "NE/CNW/SWK" or footage from lines NW NE SE
Lease Owner Don W. Jones
Lease Name Pundsack Well No. 2
Office Address 1012 Daniel Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-24 1954
Application for plugging filed 8-24 1954
Application for plugging approved 8-24 1954
Plugging commenced 8-24 1954
Plugging completed 8-24 1954
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production - 19-
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3766 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		326' 8"	5/8"	Surface casing cemented with 20 sacks cement, 1% jel, 2 Calcium Chloride		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 270' with 1/2 gallon hulls.
20 sacks of cement mixed and poured through
drill pipe. Filled hole to 35'. Top plug
at 35' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.
Address 1311 Union Nat'l Bank Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Aikins, Jr.
1311 Union Nat'l Bank Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of August, 19 54

My commission expires August 25, 1956

Leta Helm
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 19 T 21 R 13W
BOOK PAGE 29 LINE 19

9-8-54

PUNDSACK #2

LOCATION: NW $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$
 Sec. 19, 21.S, 13.W
 Stafford County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
 1311 Union Nat'l Bank Bldg.
 Wichita, Kansas

SURFACE CASING: 326' 8 5/8" with 210 sacks
 cement, 1% jel, 2 Calcium
 Chloride

OIL STRING: None

WELL LOG

0 -	75	Sand
75 -	220	Shale
220 -	280	Sand
280 -	327	Shale
327 -	800	Shale and shells
800 -	815	Anhydrite
815 -	1625	Shale and shells.
1625 -	1750	Lime and shale
1750 -	2050	Lime
2050 -	2890	Lime and shale
2890 -	2915	Junk - Lime.
2915 -	3115	Lime
3115 -	3180	Lime and shale
3180 -	3305	Lime.
3305 -	3370	Lime and shale
3370 -	3620	Lime
3620 -	3653	Lime and shale
3653 -	3689	Chert and lime
3689 -	3735	Lime
3735 -	3766	Shale and lime
3766		Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #2 Pundsack as shown in the daily drilling reports.

RECEIVED
 REGISTRATION COMMISSION
 SEP - 3 1954
 MINERAL RIGHTS DIVISION
 Topeka, Kansas

THUNDERBIRD DRILLING, INC.
 Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me this 29th day of August, 1954.

Leta Helm
 Notary Public

My commission expires:
 August 25, 1956

PLUGGING
 FILE SEC 19-21-13W
 BODY PAGE 59 LINE 19