


SP

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217



Locate well correctly on above  
Section Plat

Stafford County, Sec. 19 Twp. 21 Rge. 13 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines. SE NE SW  
Lease Owner Kenbill Oil Company  
Lease Name Pundsack #2 Well No.  
Office Address Ellinwood, Kansas 67526  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2/12/72 19  
Plugging completed 2/17/72 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 3729 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	229	none
				5 1/2"	3728	2617'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, pushed plug to 3400' and ran sand on plug, ran 5 sacks of cement. Bigged up, loaded casing with water, shot pipe at 3124', 2999', 2803', 2708', 2614', pulled 84 joints. Welded collar on 8-5/8. Allied pumped 3 sacks hulls, 15 sacks gel and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 17th day of February, 1972  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires Feb. 15, 1975  
Margaret Melcher  
Notary Public.



15.185.01987.0000

PUNDSACK #2

Casing Record:

8-5/8" - 220'  
5-1/2" - 3728'

Company: Graham-Messman-Rinehart Oil Co.  
Contractor: Aylward Drilling Company

Commenced: August 15, 1951  
Completed: August 29, 1951

Description:  
SE 1/4 NE 1/4 SW 1/4 of  
Sec. 19-21S-13W,  
Stafford County, Kansas

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Soil	0	30	
Sand	30	150	
Sand & Shells	150	185	
Blue Shale	185	220	Set 8-5/8" Csg. @ 220' and cemented with 175 sax.
Sand & Clay	220	390	
Red Bed & Sand	390	450	
Red Bed	450	600	
Sand & Shale	600	800	
Shale & Shell	800	1055	
Red Bed, Shale & Shells	1055	1445	
Sandy Lime	1445	1690	
Sandy Lime & Shale	1690	1845	
Lime & Shale	1845	2765	
Lime	2765	2800	
Lime & Shale	2800	2890	
Lime	2890	3040	
Lime Hard	3040	3085	
Lime	3085	3265	
Lime & Shale	3265	3385	
Lime	3385	3425	
Lime & Shale	3425	3470	
Lime	3470	3610	
Lime & Chert	3610	3690	5 1/2" Csg. set @ 3728' and cemented w/100 sax.
Arbuckle R.T.D.	3690	3729	

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 31 1972  
CONSERVATION DIVISION  
Wichita, Kansas

- T.D. 3729'

I certify that this is a true and correct copy of the above log.

*[Signature]*

Subscribed and sworn to before me this 5 day of September, 1951

*[Signature]*  
Notary Public

My Commission Expires

April 25, 1953

Top Perforations  
3415 to 3418