

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,931-0000

LEASE NAME Hufford

WELL NUMBER 1

SPOT LOCATION NE NW NE

SEC. 19 TWP. 21 RGE. 13XX or (W)

COUNTY Stafford

Date Well Completed 3-2-84

Plugging Commenced 3-2-84

Plugging Completed 3-2-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Formation Mechanics

ADDRESS 2110 Garland Wichita, KS 67203

PHONE # (316) 264-1501 OPERATORS LICENSE NO. _____

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Bob Dist #1 Dodge City

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3742

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 810' w/50 sacks cement thru drill pipe

Next Plug: @ 390' w/40 " " " " "

Next Plug: @ 40' w/1 sack hulls & 10 sacks cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(employee of operator) or

~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well ~~is~~ ^{is} correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

MAR 08 1984

3-8-84

SUBSCRIPTION DIVISION
Wichita, Kansas

SWORN TO before me this Feb day of 1984

Charity M. Hague
Notary Public

My Commission expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: February 26, 1984
 DATE COMPLETED: March 2, 1984

Formation Mechanics
 HUFFORD #1
 NE NW NE
 Sec. 19, T21S, R13W
 Stafford County, Ks.

ELEVATION: 1913 K.B.

0 - 807' Surface Soil, Clay, Shale,
 Sand, Red Bed
 807 - 830' Anhydrite
 830 - 2875' Lime & Shale
 2875 - 3251' Lime
 3251 - 3255' Shale
 3255 - 3271' Lime & Shale
 3271 - 3288' Lime
 3288 - 3373' Shale
 3373 - 3382' Lime & Shale
 3382 - 3598' Lime
 3598 - 3742' Shale, Lime, Chert, Sand
 3742' RID

FORMATION DATA

Anhydrite	807'
Topeka	2875'
Heebner	3251'
Toronto	3271'
Douglas	3288'
Br. Lime	3373'
Kansas City	3382'
Base K.C.	3598'
Conglomerate	3608'
Viola	3647'
Simpson Shale	3680'
Simpson Sand	3697'
RID	3742'

Surface Pipe: Set new 8-5/8"
 20# pipe @335' w/235 sacks
 50/50 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 6th day of March 1984.

My Comm. Expires:

4-29-86

Leonard Williamson

Dorothy M. Hague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 08 1984
 CONSERVATION DIVISION
 Wichita, Kansas