

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 19 Twp. 21s Rge. 13 XEX (W)

Location as "NE/CNW/SW" or footage from lines NW NE NW

Lease Owner PETROLEUM, INC.

Lease Name PUNDSACK Well No. 1

Office Address R.R. #2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL

Date well completed NOVEMBER 8 19 51

Application for plugging filed JULY 10 19 68

Application for plugging approved JULY 11 19 68

Plugging commenced JULY 10 19 68

Plugging completed JULY 15 19 68

Reason for abandonment of well or producing formation DEPLETION OF PRODUCING ZONE

If a producing well is abandoned, date of last production MAY 10 19 67

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. J. WARREN

Producing formation KANSAS CITY Depth to top 3476 Bottom 3550' Total Depth of Well 3728 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
KANSAS CITY	SLIGHT AMOUNT OF OIL & WATER	3476'	3482	8-5/8"	264'	
				5-1/2"	3727'	3043

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK FROM 3550' TO 3450' W/SAND. DUMPED 5 SACKS CEMENT FROM 3450' TO 3410'. HEAVY MUD TO 260', ROCK BRIDGE FROM 260' TO 250'. DUMPED 25 SACKS CEMENT FROM 250' TO 175', HEAVY MUD FROM 175' TO 40', ROCK BRIDGE FROM 40' TO 30', 10 SACKS CEMENT FROM 30' TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of AUGUST, 19 68

My commission expires MAY 28, 1969

Richard H. Dumbler
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15.185.01715.0000

Company- PETROLEUM, INC.
Farm- Pundsack No. 1

SEC. 19 T. 21 R. 13W
NW NE NW

Total Depth. 3728
Comm. 10-19-51 Comp. 10-31-51
Shot or Treated.
Contractor. Garvey Oil
issued. 1-5-52

County Stafford
KANSAS



Elevation. 1922 RB

Production. IPP 39 BO & 46% wtr.

CASINGS:

8 5/8" 264' cem. w/175 sx
5 1/2" 3727' cem. w/125 sx

Figures Indicate Bottom of Formations.

surface clay	40
sand	195
shale	245
sand	304
shale & sholls	410
sand	460
red bed	780
anhydrite	905
shale & shells	1500
shale & lime	1815
lime	1960
sandy lime & shale	2170
shale & shells	2685
lime	2765
lime & shale	3055
lime	3298
shale & lime	3372
lime	3575
lime & shale	3657
simpson	3670
shale	3678
lime	3728 RTD
Total Depth	

Tops:	
Hcebner	3221
Brown Lime	3341
Lansing	3352
Base-Kansas City	3555
Viola	3593
Arbuckle	3678

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas