

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.113.04532.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 3, 1965

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Smith of Flint Eng. & Const. Co. has this
date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Floyd L. King

Complete Address: Box 401, Lyons, Kansas

Lease Name: Hetzke "A" Well No. 2

Location: NE SW SE Sec. 20 Twp. 21 Rge. 1 (E) (W) X

County Mc Pherson Total Depth 3327' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 6 sacks.

Fill hole with mud to 180'. Set rock bridge from 180' to
160' and cement hole to base of cellar with 5 yards ready-
mix cement.

Very truly yours,

A handwritten signature in dark ink, appearing to read "R. C. Londerholm", written over a horizontal line.

Conservation Division Agent