



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Cleary Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum Inc.

Complete Address: 310 Kermac Bldg. Okla. City, Okla.

Lease Name: Hildebrand Well No. # 1

Location: NE NE Sec. 16 Twp. 21 Rge. 38 (E)(W)

County Kearny Total Depth 5087' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8"-306' Circulated w/cement. 5 1/2"-5087' Cemented.

Plug bottom w/20 Sax. cement top cement 4800'. Mud 4800' to 700'

Spotted 25 Sax. cement 700' to 625'. Mud 625' to 325'

Spotted 25 Sax. cement 325' to 250'. Mud 250' to 35'

Plug, 10 Sax. cement 35' to 0

Very truly yours,

Conservation Division Agent