



15-113-20608-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

December 9, 1978

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1978

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Don Rogers of Kan-Go, Inc. has this date requested permission to plug the following described well:

Mr. Rogers guarantees payment of the plugging fee.

Operator's full Name: Charles Carlock

Complete Address: 1515 Hillcrest Rd., Newton, Kansas

Lease Name: WITTER Well No. 1

Location: C NW NW Sec. 24 Twp. 21 Rge. 2 (E)(W) X


County: McPherson Total Depth 3375 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rogers was instructed to plug the well as follows:

8 1/2" - 202' - w/150 sacks cement. Fill hole with mud to 190'. Push plug and 1/4 sack hulls to 190' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and clog hole with 10 sacks cement. Bridge rathole and mouse hole and cement with a total of 5 sacks.

Very truly yours,


Conservation Division Agent