



15.113.00578.0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

November 4, 1964  
**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 9 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Wayne Dobbs of Vaughan Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Burch Exploration, Ltd.

Complete Address: 1011 Union Center, Wichita, Kansas

Lease Name: Buller Well No. 1

Location: SE SE NW Sec. 14 Twp. 21 Rge. 4 (X) (W) X

County Mc Pherson Total Depth 3913' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Dobbs was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]  
Conservation Division Agent