


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 3 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SW
Lease Owner Commercial Oil Co.
Lease Name Rainey Well No. 4
Office Address 5252 N. Broadway Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 8-25 1970
Application for plugging approved 8-25- 1970
Plugging commenced 8-28- 1970
Plugging completed 9-3- 1970
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 3413 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7" 3/4	3406	2200
				10" 7/8	172	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Sand from 3413 to 3400 - dump 6 sax cement - pull 2200 ft. 7".
Rock bridge from 280 to 260 ft. - dump 4 1/2 yds ready mix cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. Permit # 490
Address Stafford, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.
Ralph Comstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Comstock
Stafford, Kas.
(Address)

SUBSCRIBED AND SWORN to before me this 2 day of Oct, 1970

My commission expires Nov 30th 1970
Bryan J. Jones Notary Public.

STAMPED

ORIGINAL

JAN 19 1946

15.159.04348.0000

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1970
CONSERVATION DIVISION
Wichita, Kansas

H. C. Bennett
Contract #1 *Rainey #4*

3 - 21 - 6W
Sec. 3 Twp. 21 Rge. 6 W
County: Rice, Kansas
C 9/2 SW (C 5/2 SW)
cut 175 B & B

Total Depth: ~~3700'~~
Comm: 1/13/45 Comp: 2/11/45

Casing
7 Jts. 10 3/4" Set at 172'
7" 3406

Cement
175 Sacks ✓

Formation:	Depth:
Sand, Clay, & Shale	65'
Shale & Shells	100
Shale, Shells, & Sand	191
Red Bed & Shale	250
Anhydrite & Shale	250
Shale & Shells	345
Salt	750
Shale & Salt	255
Shale & Shells	950
Lime	1040
Shale & Shells	1070
Shale, Shells, & Lime	1325
Shale & Lime	1625
Broken Lime & Shale	1865
Shale & Shells	2100
Lime, Shells, & Shale	2250
Lime & Shale	2470
Lime	2625
Sandy Shale	2730
Lime & Shale	2845
Lime	3222
Lime & Shale	3347
Shale & Red Rock	3582
Redrock, Shale, & Conglomerate	3401
Chat	3409 13

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Clara F. Linnell

Subscribed and sworn to before me this 16th day of February, 1945.

Genevieve Pool
Notary Public
My comm. expires 7/2/45