

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY McPherson SEC. 27 TWP. 21 RGE. 3W E/W
Location as in quarters or footage from lines:
SE/4 SW/4 SW/4

Lease Owner Brunson-Spines, Inc.
Lease Name Ratzlaff Well No. 1
Office Address 525 Fourth Financial Center, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 12/3/81
Application for plugging filed _____
Plugging commenced _____
Plugging completed 12/3/81
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merlan Unruh, Halstead, Ks.
Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Silt & Clay		0	25'	8 5/8"	25'	None
Sand		25'	130'	8 5/8"	105'	None
Shale		130'	180'	8 5/8"	50'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with mud to 200' and put in 1/2 sacks of hulls and cemented plug with
30 sacks of cement, Filled hole with mud to 40' and put in 1/2 sack of hulls. Cemented
plug with 12 sacks of cement, 5 sacks of cement in rathole. Plugging completed
at 2:00 P. M., December 3, 1981 by State Plugger, Merlan Unruh, Halstead, Kansas.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc., P.O. Box 1184, McPherson, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Brunson-Spines, Inc. (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God. BRUNSON-SPINES, INC.

(Signature) Ed S. Brunson
BY: Ed S. Brunson
525 Fourth Financial Center
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1981

Donald E. Crawford
Notary Public.

My Commission expires: 6/9/85



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

December 4, 1981

COMPANY: BRUNSON-SPINES INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: RATZLAFF #1
 LOCATION: SE/4 SW/4 SW/4 Section 27-21-3W,
 McPherson County, Kansas
 COMMENCED: November 25, 1981
 COMPLETED: December 3, 1981
 ELEVATION:

0	to	25	Silt & Clay
25	to	130	Sand
130	to	180	Shale
180	to	1900	Shale & Lime
1900	to	2110	Lime & Shale
2110	to	2560	Lime
2560	to	2765	Lime & Shale
2765	to	2960	Shale & Lime
2960	to	3119	Lime & Shale
3119	to	3290	Mississippi
3290	to	3354	Mississippi Lime
3354	to	3375	Kindershook Shale
3375	to	3480	Shale
		3480	T. D.

Cut 12 1/2" hole to 178' and run 180' of 8 5/8" surface casing, cemented with 150 sacks of cement at 178'. Plug down at 11:00 A. M., November 25, 1981. Hole dry and abandoned. Filled hole with mud to 200' and put in 1/4 sack of hulls and cemented plug with 30 sacks of cement. Filled hole with mud to 40'. Put in 1/4 sack of hulls & cemented plug with 12 sacks of cement., 5 sacks in rathole. Plugging completed at 2:00 P. M., December 3, 1981. State Plugger, Marian Unruh, Halstead, Kansas.

TOPS: MISSISSIPPI - 3119'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Ratzlaff #1, located on the SE/4 SW/4 SW/4 Section 27-21-3W, McPherson County, Kansas.




P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 4th day of December, 1981.



Johnnie L. Schmidt - Notary Public



RECEIVED
STATE OF KANSAS COMMISSION

JAN - 4 1982

CONSERVATION DIVISION
Wichita, Kansas



Fud Mud, Inc.

15-113-20935.0000

Nº 10551

767 Oil Hill Road

El Dorado, Kansas 67042

316/321-1397

316/321-9508

Sold To:

Blackstone #3

Branson & Spines Inc.

Ratzlaff #1

API 15-013-20935

Date	Salesman	Lease Name & No.
<i>12-3-81</i>	<i>Robin</i>	

270 Bestolife

ZN 50 Bestolife

Trulifine Rig Wash

Rags

#1 Tubing Brush

#3 Wire Brush

#7 Scrub Brush

#8 Scrub Brush

Sample Bags

47 Cement

2 8 5/8 Plugs

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1981
CONSERVATION DIVISION
Wichita, Kansas

Received By:

Allen D Beck