

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bittling Building,
Wichita, Kansas.

RECEIVED

FEB 7 1936


BY

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
640 A. Plat

Rice County. Sec. 33 Twp. 21S Rge. 6W (E) (W)

Lease Name Tharp
Lease Owner Taber & Coleman
Office Address 605 Amarillo Bldg. Amarillo, Tex.
Character of Well (Oil, Gas or Dry) Dry Total Depth of Well 4097 Feet
Date, well, completed Jan. 28th 36
Application for plugging and log of well filed Same Jan. 28th, '36 193
Application for plugging approved Same 193
Plugging Commenced Same 193
Plugging Completed Same 193
Reason for abandonment of well or producing formation Dry

WELL NO. 1

If a producing well is abandoned, date of last production 193
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Officer who supervised plugging of this well Raymond Gear
Producing formation Depth to top Bottom

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size hole	Put In	Pulled Out
Kansas City Lime		2925	3275	8 1/2"		
Chat	water	3584		"		
Viola		3952	4000	"		
Simpson		4000	4072	"	none	
Sileaceous	water	4000	4097	"		
Surface sand	water	0	65	13 3/4"	10"	165' cemented.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated with a mixture of Baroco, Aquagel and natural mud weighing approximately 12 # to the gallon. Put plug in 10" surface pipe and put in 18 sacks of cement above plug.



(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes
Was exception made? No If so describe.

Correspondence regarding this well should be addressed to Philip Taber
Address 1918 E 30th Pl. Tulsa, Okla.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Philip Taber (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Philip Taber
1918 E 30th Pl. Tulsa, Okla. (Address)

SUBSCRIBED AND SWORN to before me this 6th day of February, 1936

My commission expires June 26, 1939 J. L. Briggs Notary Public.

WELL RECORD

RECEIVED
FEB 13 1936

33-8

Block or Twp. 21 South - 6 West

Well No. 1

State Kansas

Elevation Feet

Lease THARP
Lease No. KS-5173
County RiceDrilled { Contract X
Company ToolsContracted Depth
Completed Depth 4097Feet
Feet Date { Started November 28, 1935
Completed January 29, 1936
Deepened
Cleaned Out

Name of Contractor Tabor & Coleman

Contract Price Per Foot

Day Work

Well Estimated Cost
Well Actual Cost

Method of Drilling ROTARY

BEFORE SHOOTINGAFTER SHOOTINGinitial Production
Settled ProductionFlowing
on PumpInitial Production
Settled ProductionFlowing
on Pump

Baume Test DRY

Water With Oil %

Casing RecordTorpedo Record

SIZE	SET	PULLED	Date	Company	From	To	Feet	Size of Shell	Total Qts.
10"	156'	None							
	Set with								
	150 sac								
	cement								

FORMATIONTOP BOTTOM

Soil	0	10
Shale and shell	10	625
Shale, shell and salt	625	805
Shale, shells and lime	805	1035
Broken lime	1035	1305
Lime and shale	1305	1330
Shale	1330	1375
Lime	1375	1445
Shale	1445	1450
Lime and shale	1450	1490
Lime	1490	1560
Shale and shells	1560	1700
Lime and shale	1700	1775
Shale, limeshells	1775	1985
Shale & shells	1985	2070
Lime and shale	2070	2190
Lime	2190	2220
Shale	2220	2235
Lime	2235	2260
Shale	2260	2300
Lime	2300	2305
Shale	2305	2335
Shale and lime	2335	2435
Lime	2435	2470
Shale	2470	2490
Lime	2490	2575
Lime	2575	2582
Shale	2582	2586
Lime	2586	2780
Shale	2780	2900
Lime and shale	2900	2925
Chert, lime and shale	2925	2935
Lime	2935	3070

County **Rice**
 Farm **THARP**
 Owner **Atlantic, Etal.**

State **Kansas**
 Well No. **1**

File
 Elevation

Formation	TOP	Bottom	Remarks
Shale	3070	3110	
Lime	3110	3195	
Shale	3195	3200	
Lime	3200	3210	
Shale	3210	3220	
Lime	3220	3230	
Shale	3230	3250	
Lime	3250	3275	
Shale	3275	3285	
Lime	3285	3404	
Red rock	3404	3410	
Lime and shale	3410	3425	
Lime	3425	3460	
Lime and shale	3460	3582	
Lime	3582	3584	
Chat	3584	3684	
Chat and Lime	3684	3708	
Chat	3708	3723	
Chat and shale	3723	3773	
Shale	3773	3906	
Lime	3906	3928	
Shale	3928	3952	
Lime	3952	3967	
Shale	3967	3971	
Lime (Viola)	3971	3997	
Green shale	3997	4000	
Simpson Sand	4000	4010	
Chert and sand	4010	4028	
Lime and sand	4028	4040	
Lime and sand	4040	4048	
Lime and sand	4048	4072	
Siliceous Lime	4072	4097	

Total Depth - Plugged and Abandoned
 January 29, 1936