


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 25 Twp. 21 Rge. 8 (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines C NE NE
Lease Owner Isern-Wells Bull Creek
Lease Name Swartz Estate Well No. 4
Office Address Box 486, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed Nov. 8 19 73
Application for plugging approved _____ 19____
Plugging commenced Jan. 24 19 74
Plugging completed Jan. 29 19 74
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	268'	8 5/8"	268'	none
			3450'	5 1/2"	3450'	2671.79

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3370' and dumped 5 sacks of cement.
Set 10' rock bridge at 265'. Plugged well with 35 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON SS.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 74

My commission expires Feb. 10, 1975
George A Meyer Notary Public.

WELL LOG AND RELATED DATA

DIVISION Northern Producing DISTRICT Oklahoma City LEASE Swartz Estate
 ACRES 140 LEASE NO. 28833 AFE NO. 4560 ELEVATION Crd. 1618' D.P. 1621' WELL NO. 4
 LOT-SEC. 25 TWP. 21 S RGE. 8 W PRCT.-DIST.-YWP. (Bull Creek Miss. Pool)
 SURVEY (Bell Prospect) COUNTY Rice STATE Kansas

LOG			
FROM	TO	TOTAL	FORMATION
0	70	70	Sand
70	269	199	Redbed & Sand
269	730	461	Shale
730	1150	420	Shale & Shells
1150	1345	195	Shale & Lime
1345	1525	180	Lime
1525	1700	175	Lime & Shale
1700	2030	330	Shale
2030	2521	491	Shale & Lime
2521	2675	154	Lime
2675	2959	284	Lime & Shale
2959	3383	424	Lime & Chert
3383	MISS	CHAT	(E.L. Top)
3383	3460	77	Chert & Shale
3460			TOTAL DEPTH
	PLUGGED BACK		
3460	3442	18	Cmt. 5 1/2" Casg.
3442			TOTAL DEPTH - PB
			(All measurements taken from top of rotary bushing which is 3' above derrick floor.)
	PAY ZONE		
3383	3402		

LOCATION

1620 FEET NORTH OF SOUTH SECTION LINE
 4620 FEET EAST OF WEST SECTION LINE
 660 FEET SOUTH OF NORTH SECTION LINE
 660 FEET WEST OF EAST SECTION LINE

SCALE 2" = 1 MILE

RECEIVED NOV 9 1973
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

CASING AND CEMENTING RECORD

SIZE CASING	8 5/8"	5 1/2"
THREAD	8 rd.	8 rd.
WEIGHT	28#	11#
GRADE	J-55	J-55
CONDITION	A	A
SET AT	268'	3450'
SACKS CEMENT	200	125
SIZE OF HOLE	12 1/4"	7 7/8"

(Temp. survey 1-2-62 indicated top of cement behind 5 1/2" casing at 2700')

LINER RECORD

SIZE	WT.	COND.	LENGTH	BLANK	PERF.	SET AT

GUN PERFORATING RECORD

DATE	CASING	FROM	TO	SIZE SHOTS	NO. SHOTS
1-4-62	5 1/2"	3383	3402	Jat.	38

SHOT OR ACID RECORD

DATE	TOP	BOTTOM	SHOT-ACID	REMARKS
1-6-62	3383	3402	500g MA	

DRILLING: COMMENCED 12-23-61 COMPLETED 1-1-62

ELECTRICAL SURVEY BY (1) DATE

DRILLED WITH (Gabbert - Jones) Rotary TOOLS

DRILLED IN WITH (Gabbert - Jones) Rotary TOOLS

FIRST PROD. - NAT. DATE None HRS. BBLs. OIL

WATER SHOT 1-17-62 M CU. FT. GAS 24 LBS. ROCK PRESS. 48 OIL

FIRST PROD. AFTER ACID - DATE 0 WATER - M CU. FT. GAS - LBS. ROCK PRESS. -

GAS/OIL RATIO - POTENTIAL 48 Oil No Wtr. BBLs.

GRAVITY 33.8 TEMP. 60° GRADE Mid-Continent

(1) 12-31-61 - Schlumberger (Laterolog & Sonic) 3450'

DATE ABANDONED - SOLD 19