

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sterling Drilling Company

Complete Address Box 129 Sterling, Kansas 67579

Lease Name Johnson "A" Well No. 8

Location E/2 SE NE Sec. 4 Twp. 21 Rge. 6 (E) (W)

County Rice Total Depth 3491'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling

Address Chase, Kansas License No. 624

Operation Completed: Hour 11 AM Day 6 Month 10 Year 71

The above well was plugged as follows:

8 5/8"-106'-Circulated w/cement. 5 1/2"-3490'-Cemented. Plug back to 3461'.

Top Perf. 3418'. Sand hole to 3400'. 5 Sax. Cement 3400' to 3350'.

Mud 3350' to 190'. Bridge 190' to 180'. 35 Sax. cement 180' to 75'.

Mud 75' to 40'. Bridge 40' to 30'. 10 Sax. cement 30' to 0.

Pulled 2911'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10-8-71

INV. NO. 4440-W