

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sterling Drilling Co.

Complete Address Box 129 Sterling, Kansas 67579

Lease Name Johnson A Well No. 2

Location NW SE NE Sec. 4 Twp. 21 Rge. 6 (E)/ (W)

County Rice Total Depth 3439'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas License No. 624

Operation Completed: Hour 4 PM Day 2 Month 10 Year 71

The above well was plugged as follows:

8 5/8"-105'-Circulated w/cement. 5 1/2"-340'-Cemented. Sand hole to 3390'.
5 Sax.cement 3390' to 3350'. Mud 3350' to 190'. Bridge 190' to 180'.
35 Sax.cement 180' to 80'. Mud 80' to 40'. Bridge 40' to 30'.
10 Sax.cement 30' to 0. Pulled 1612'-5 1/2"- pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: *Hughes*
Well Plugging Supervisor

INVOICED

DATE 10/5/71
INV. NO. 4409-4