

15.159.04366.0000

Form CP-3
Rev. 6-4-68

KANSAS

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sterling Drilling Company

Complete Address P.O. Box 129, Sterling, Kansas 67579

Lease Name Johnson "A" Well No. 1

Location SE NE NE Sec. 4 Twp. 21 Rge. 6 (E) (W)X

County Rice Total Depth 3427'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 5 PM Day 27 Month September Year 1971

The above well was plugged as follows:

Hole filled with sand to 3380' and cemented with 5 sacks cement.

Hole bailed to 210'. Rock bridge set from 210' to 200' and hole cemented with 35

sacks cement (top 100'). Hole filled with mud to 40'. Rock bridge set from 40' to

30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. D. Lawrence*
Well Plugging Supervisor

DATE 9-29-71

INV. NO. 4384-W