

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sterling Drilling Company

Complete Address: P.O. Box 127, Sterling, Kansas

Lease Name Cleavinger Well No. 7

Location SE NW NW Sec. 4 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3427'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: P.O. Box 405, Chase, Kansas License No. 405

Operation Completed: Hour 2 PM Day 1 Month April Year 1966

The Above well was plugged as follows:

Hole filled with sand to 3400' and cemented with 5 sacks.

Hole filled with mud to 210'. Rock bridge set from 210' to 200' and hole cemented

with 25 sacks. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and

hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *William J. Leonard*
Well Plugging Supervisor

DATE 4/5/66

INV. NO. 2991-w