

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-1-68

RECEIVED  
STATE CORPORATION COMMISSION

DEC 06 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 159-04299.0000 (of this well)

Operator's Full Name Phillips Petroleum Company

Complete Address 7th Floor Frank Phillips Bldg., Bartlesville, Okla 74004

Lease Name Alexander "F" Well No. 5

Location SW NE NW Sec. 4 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3457'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling, Halliburton Co. and Sun Cementing Co.

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 2:30 PM Day 28 Month November Year 1977

The above well was plugged as follows:

Hole filled with sand to 3434. Pumped 25 sacks gel and 50 sacks cement  
through tubing at 3422'. Pumped 25 sacks gel and 20 sacks cement  
through 5½" casing at 2615'. Pumped 8 sacks gel at 273'. Pumped 35 sacks  
cement through tubing at 213'. Pumped 15 sacks cement through tubing at  
41' and cement circulated into cellar.

2743' of 5½" casing recovered.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 12-8-77

INV. NO. 6317-C