

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 06 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-159-05257.0000 (of this well)

Operator's Full Name Phillips Petroleum Company

Complete Address 7th Floor Frank Phillips Bldg., Bartlesville, Okla. 74004

Lease Name Alexander "F" Well No. W-3

Location NE NE NW Sec. 4 Twp. 21 Rge. 6 (E) (W)X

County Rice Total Depth 3463'

Abandoned Oil Well Gas Well Input Well X SWD Well ≠ D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling, Halliburton Co., and Sun Cementing

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 11:30 AM Day 28 Month November Year 1977

The above well was plugged as follows:

Hole filled with sand to 3420'. Hole circulated with mud. 50 sacks
cement pumped through tubing at 3420'. Pipe shot at 2005'. 25 sacks
cement pumped through casing at 2005'. 15 sacks gel pumped through casing
above cement.. Pumped 12 sacks gel through tubing at 482'. Pumped 35 sacks
cement through tubing at 212'. Pumped 15 sacks cement through tubing at
42', cement circulated into cellar.

2005' of 5½" casing recovered.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-8-77
INV. NO. 6312-C